

Example of “Ductility” of Skidmark Geomembrane® irrigation ditch/canal lining

The top left photo shows liner after installation and before water on from downstream end. Right photo shows liner molded to ditch after second water season. Bottom photos are of the same area from the upstream end.



The liner in this installation was secured along the berms with rebar. Backside bank and narrow front side berm prevented the use of anchor trenches required by most liner suppliers. Further, the liner is performing well in this nearly half-pipe ditch profile with vertical sides.

When ideal site preparation is not practical, Skidmark Geomembrane may be the solution.